



Hyundai Motor America

Building Use: Office Building
Scope of Work: Waterproofing

Project Data

Location
Fountain Valley, CA

Owner
Hyundai Amco America Inc.

Project Value
\$677,685

Completion Date
June 2014



This project involves the replacement of Hyundai's existing North American Corporate Headquarters with an expanded 469,700 square foot corporate campus which will accommodate a similar range of uses as the existing facility. The construction will include a sis-level office building, a single-level technical service building, a four-story parking structure and surface parking.

BEST was selected to perform above-grade waterproofing at various locations, including site retaining walls, elevator pits, fire water storage tank, perimeter curbs, tech center perimeter, roof and garden court. American Hydrotech 6125 Hot Rubber, membrane and Cementitious waterproofing was used for this project.

The membrane system of 100% solids elastomeric urethane, including applicable sealants and elastomeric flashings, needed to ensure a complete waterproof system at the water tank locations, floors, walls and lid.

